

Bill of Quantity for Removing and Installation of high-pressure compressed air Pipe along with two fuel pipe lines from WALMI to Permanent Campus IIT Dharwad

Sl No	Description of Item	UoM	Qty	Rate ₹	Amount ₹
1	<p>Dismantling and reinstallation of SS316 1" and 1/4" gas tubing as per site conditions.</p> <p>1. Seamless tube 1/4" ODx 1mm THK SS316L both side EP OD Tube - 6 meter</p> <p>2. Seamless tube 1" ODx 1.2mm THK SS316L both side EP OD Tube - 6 meter</p> <p>3. SS316 1/4" NPTM to 1/4" OD (for regulator outlets fittings) - 10Nos</p> <p>4. SS316 1/4" OD Union - 10 Nos</p> <p>5. SS316 1/4" OD Tee - 4 Nos</p> <p>6. SS316 1/4" OD Ball Valve - 4 Nos</p> <p>7. SS316 1" OD to 1/2" BSPM - 4 Nos</p> <p>8. SS316 1" OD Union - 6 Nos</p> <p>9. SS316 1" OD Tee - 2 Nos</p> <p>10. SS316 1" OD Elbow - 4 Nos</p> <p>11. SS316 1" OF Ball valve - 1 Nos</p> <p>12. SS316 1/4" OD Ferrules - 30 Nos</p> <p>13. SS316 1/4" OD Ferrules - 10 Nos</p> <p>14. Accessories such as a Profile, Tule holding clamp and Tags Hardware Material Hardware like Unistrut Channel, with Rail Nut (For all size of tubes as per BOQ), Aluminium Profile, PP End Caps, M10 GI Threaded Rod, M10 GI Plane Washer & Nut, M 10 GI Anchor Bolt for Threaded Rod, Channel GI, MS ISA, Anchored Plate MS (IS 2062 Steel), M12 Bolts including Fabrication work (High tension HILTI, all above mentioned items & accessories. 1 Lot</p>	Nos	1		
				TOTAL ₹	
				GST ₹	
				GRAND TOTAL ₹	

